



- GENERAL NOTES:
1. ALL UTILITY WORK MUST COMPLY WITH CURRENT CITY STANDARDS AND SPECIFICATIONS.
  2. ALL ASPHALT WORK MUST COMPLY WITH CURRENT CITY SPECIFICATIONS PER MCC 11-10-4.

- KEYED NOTES:
1. INSTALL 2" GAS LINE
  2. INSTALL 8" C-900 PVC WATERLINE
  3. INSTALL 4" C-909 PVC P.I. LINE
  4. INSTALL 8" PVC IRRIGATION LINE (GRAVITY FLOW)
  5. INSTALL STORM DRAIN SUMP
  6. INSTALL PRE-TREATMENT INLET BOX
  7. INSTALL 8" PVC (SDR-35) SEWER LINE
  8. INSTALL 4" PVC (SDR-35) SEWER LATERAL (TYP)
  9. INSTALL WATER SERVICE (AS PER CITY STANDARD) (TYP)
  10. INSTALL 18" ROLLED GUTTER
  11. INSTALL 4" CROSS GUTTER WITH FORD
  12. INSTALL P.I. SERVICE (TYP)
  13. SAWCUT EXISTING ASPHALT AND INSTALL NEW PAVEMENT TO GUTTER
  14. INSTALL FIRE HYDRANT ASSEMBLY
  15. INSTALL BLIND FLANGE PLUG ON TEE
  16. 120' HAMMERHEAD FIRE TRUCK TURNAROUND

NORTH

Richard A. Hatfield  
5-2-25  
2774512  
LICENSED PROFESSIONAL ENGINEER  
STATE OF UTAH

0 15 30 60 90  
DRAWING SCALE (SHEET SIZE 24X36): 1" = 30'

**APEX**  
Engineering, Inc.  
661 NORTH MAIN STREET SPANISH FORK, UT 84111  
apex20.com 801-796-2277

REVISIONS

MARK	DATE	REMARKS
▲	-	-

EAST HILL MEADOWS (MAIN).DWG 5/21/25 1:53 PM

PROJECT: EAST HILL MEADOWS

LOCATION: MONA, UTAH

SUBMITTAL TYPE: PRELIMINARY APPROVAL

SHEET: PRELIMINARY PLAT DRAWING: C-0